

# SOLAR WATER HEATER

DATE	ITEM	QTY	COST	NET	FROM	PANELS	TANK
11/18/2009	1/2" COPPER ELBOW	4	0.37	1.48	H/D	\$1.48	
11/18/2009	1/2" COPPER TEE	27	0.64	17.28	H/D	\$17.28	
11/18/2009	1/2" OSB	2	5.97	11.94	H/D	\$11.94	
11/18/2009	1/2" RIGID COPPER 10' TUBE	14	7.03	98.42	H/D	\$98.42	
11/18/2009	1/2" TUFF-R	2	10.63	21.26	H/D	\$21.26	
11/18/2009	2X6X10 TREATED	5	5.97	29.85	H/D	\$29.85	
11/18/2009	SOLDER 1LB	1	13.77	13.77	H/D	\$13.77	
11/20/2009	1/2" X 10' RIGID COPPER	2	7.03	14.06	H/D	\$14.06	
11/20/2009	1/2X1/2X3/4 COPPER TEE	2	6.05	12.10	H/D	\$12.10	
11/20/2009	3/4" COPPER ELBOW	2	0.81	1.62	H/D	\$1.62	
11/20/2009	3/4" COPPER TO 3/4" PVC ADAPTER	2	3.19	6.38	H/D	\$6.38	
11/20/2009	3/4"X10' RIGID COPPER	1	11.60	11.60	H/D	\$11.60	
11/20/2009	PROPANE	2	2.95	5.90	H/D	\$5.90	
11/24/2009	PLATING & TWIN/WALL	1	152.00	152.00	T.S.	\$152.00	
11/25/2009	1" DRYWALL SCREW PER LB	2.03	2.49	5.05	TRUE VALUE	\$5.05	
11/25/2009	1/2" COPPER UNION	2	0.59	1.18	TRUE VALUE	\$1.18	
11/27/2009	1" DRYWALL SCREW PER LB	1	2.49	2.49	TRUE VALUE	\$2.49	
11/27/2009	1/2" CONDUIT	1	1.35	1.35	H/D	\$1.35	
11/27/2009	QT FLAT BLACK PAINT	1	8.96	8.96	H/D	\$8.96	
11/27/2010	FLAT BLACK SPRAY PAINT	6	3.99	23.94	NAPA	\$23.94	
12/1/2009	WEATHERSTRIP	3	1.99	5.97	NAPA	\$5.97	
12/14/2009	4X8X1" STYROFOAM	9	10.49	94.41	H/D		\$94.41
12/14/2009	4X8X1/2" TUFF-R	2	10.63	21.26	H/D		\$21.26
12/14/2009	GREAT STUFF	2	3.83	7.66	H/D		\$7.66
12/15/2009	15'X52" POOL LINER	1	87.87	87.87	POOL GEAR PLUS		\$87.87
12/15/2009	3/4" AQUAPEX	300	0.56	167.35	PEX SUPPLY		\$167.35
12/15/2009	GRUNDFOS PUMP	1	72.95	72.95	PEX SUPPLY		\$72.95
12/15/2009	GRUNDFOS PUMP FLANGES	1	7.15	7.15	PEX SUPPLY		\$7.15
12/15/2009	PEX FREIGHT	1	31.81	31.81	PEX SUPPLY		\$31.81
12/15/2009	PEX TO PIPE ADAPTERS	2	4.65	9.30	PEX SUPPLY		\$9.30
12/18/2009	1/2" TUFF-R	1	10.63	10.63	H/D		\$10.63
12/18/2009	GREAT STUFF	1	3.83	3.83	H/D		\$3.83
12/18/2009	PVC PIPE	3	1.18	3.54	H/D		\$3.54
12/22/2009	3/4" CPVC 45 ELBOW	2	0.46	0.92	H/D		\$0.92
12/22/2009	3/4" CPVC ELBOW	14	0.39	5.46	H/D		\$5.46
12/22/2009	3/4" CPVC MALE ADAPTER	2	0.39	0.78	H/D		\$0.78
12/22/2009	3/4X10 CPVC	2	5.38	10.76	H/D		\$10.76
12/22/2009	PIPE INSULATION	10	1.86	18.60	H/D		\$18.60
12/28/2009	3/4 CPVC ELBOW	4	0.39	1.56	H/D		\$1.56
12/28/2009	3/4X10 CPVC	2	5.38	10.76	H/D		\$10.76
12/28/2009	CPVC CPLR	2	0.26	0.52	H/D		\$0.52
12/28/2009	CPVC ELBOW	2	0.46	0.92	H/D		\$0.92
12/28/2009	CPVC ELBOW	4	0.39	1.56	H/D		\$1.56
12/28/2009	CPVC FEMALE CPLR	2	0.99	1.98	H/D		\$1.98
12/29/2009	CUT-OUT SWITCH	1	14.85	14.85	CONTROLS SUPPLY		\$14.85
						\$446.60	\$586.43

**Grand Total**

**\$1,033.03**